

**JEMM Construction, LLC**  
**200 Blackbrook Road**  
**Painesville, OH 44077**  
**O | P (440) 358-0008**  
**www.jemmconstruction.net**



## **ESSENCE BUILDING FEATURES**

### **Site Work**

- 50' Front Setback
- City Water & Sewer

### **Foundation**

- 9' Tall Textured poured concrete foundation
- 30 year Limited waterproof warranty (per manufacturer)
- Interior & Exterior drain tile around footings

### **Framing**

- 2"x 6" exterior wall construction at 16" on center
- 9'+ Tall First Floor ceiling height (ceiling details per specifications)
- House Wrap for wind & water-resistive barrier
- Raised energy heel at roof for superior energy performance
- 3/4" Edge Gold tongue and groove O.S.B. flooring (swell resistant no sanding)
- 1/2" O.S.B. roof sheathing and 7/16" O.S.B. wall sheathing

### **Windows & Doors**

- Simonton ProFinish DH windows Low-E with Argon Gas energy package with grids on front elevation
- Therma-Tru Fiberglass paintable exterior doors
- 8' tall Haas 600 Series Insulated Overhead Garage Door
- LiftMaster 1/2 hp Chain Drive Garage Door Opener w/ Built-in WiFi/MyQ technology

### **Roofing**

- Owens Corning Oakridge AR Limited Lifetime Shingles

### **Masonry**

- ProVia Stone veneer on Front Elevation (up to 25% of front & to grade based on deed restrictions)

### **Siding & Gutters**

- Choice of colors from JEMM selections of .044 thickness Clap Board or Dutch Lap Vinyl Siding
- 5" seamless aluminum gutters with 2"x 3" aluminum downspouts

### **Exterior Concrete**

- 16' wide x 4" thick driveway to road with fibermesh reinforcement & broom finish
- 4' wide x 4" thick walkway from driveway to front step

## **Plumbing**

- Rinnai Sensei RU160iN Tankless Water aheater (REU-N2530FF)
- Waterline to refrigerator
- Moen 1/2 hp Garbage Disposal
- Zoeller Sump Pump
- Ejector Crock & Grinder Pump (if required by municipality)
- Full Bath Drain Lines Rough-In in Basement
- Moen Plumbing Fixtures
- Stainless Steel undermount sink in Kitchen supplied by Granite Supplier
- Tile Shower in Master Bathroom with Handheld Slidebar and Diverter Valve
- Fiberglass Tub/Shower in Full Bathrooms
- Mansfield Alto Elongated Toilets (SmartHeight in Master & Half Bath)
- Ceramic Oval sinks in bathrooms (undermount on granite tops & drop in on laminate tops)
- Mansfield Alto IV 24" pedestal sink in Half Bath
- Laundry Tub in Laundry Room
- Shut-off valves at all sinks & toilets
- Hot & Cold Spigot in Garage
- 1 - 8"Garage Floor Drain

## **HVAC**

- Lennox 96% high-efficiency gas, forced air furnace
- Lennox 13AXC energy-efficiency air conditioner
- Mechanical Fresh Air Ventilation
- Digital screen thermostat

## **Electrical**

- 200 amp Electrical Service
- Arc fault protectors per code
- Toggle style switches
- Tamper resistant outlets
- Wiring for ceiling fans in bedrooms w/ 2 switches
- 7 - CAT5 &/or RG6 (phone/data jacks)
- 2 - USB Outlets
- 1- Floor Outlet
- 12 - 6" Recessed Lights
- 4 - Under Cabinet Lights
- 1 - Wall Oven Outlet
- Smoke Detectors centrally wired with battery back-up on each floor & each bedroom
- Carbon Monoxide Detector at each floor

## **Fireplace**

- Majestic 36" Quartz Direct Vent Fireplace System

## **Insulation**

- R-19 Fiberglass Batt Insulation w/ PureFiber Technology in exterior walls & basement rim joists
- R-49 Blown-in Insulation in attics
- R-11 Blanket Insulation in basement 4' from top of foundation wall down
- Air infiltration on all exterior walls - caulk corners & plates & closed cell foam electrical boxes

### **Drywall**

- House - 1/2" Drywall - all walls & ceilings w/ stipple texture on all ceilings & non-walk-in closets
- Garage - 5/8" Drywall per fire code w/roll texture walls & stipple ceiling texture
- Green Board per code at wet locations

### **Cabinetry & Counter Tops**

- JEMM Level 2 - Avalon Maple & Sinclair Birch & Series (stained or painted) Kitchen & Master Bath
- 36" Tall wall cabinets with crown moulding in Kitchen
- Wood dovetail full extension soft close drawers & soft close doors in Kitchen & Master Bath
- 1 Drawer Base & 1 Pull Out Garbage Can in Kitchen
- Choice of Cabinet Hardware from JEMM Cabinet Hardware Selections
- JEMM Level 2 - Granite or Quartz Counter Tops w/4" Backsplash in Kitchen

### **Interior Finishes**

- Oversized 3-1/2" MDF Colonial Casing
- Oversized 5-1/4" MDF Colonial Baseboard
- Choice of Poplar Railing from JEMM Trim Selections
- Choice of Matt Black Metal stair spindles from JEMM Trim Selections
- Choice of Poplar Box Newel Posts from JEMM Trim Selections
- Choice of JELD-WEN 6'-8" tall solid core door styles
- Poplar Box Beam Fireplace Mantle with Legs
- Mantle and Railing stained with 4-stage application, hand sanded, putty nail holes and varnished
- 4' Bench with upper Cubbies
- Yale New Traditions interior door levers or knobs (Choice of several styles and colors)
- Yale McKinley front door handle set
- Deadbolts on all exterior doors
- 3 Wall paint colors (flat finish)
- Trim paint semi-gloss
- Light Stipple Textured Ceilings painted one coat flat white

### **Shelving & Hardware**

- 1/4" plate glass mirrors at each vanity
- Wire Shelving in all closets (tight mesh in pantry)
- Moen towel bars & tissue holders in all baths
- Splendor single hinged shower door

### **Flooring**

- Choice of carpet in all bedrooms & bedroom closets, upstairs hallways
- High traffic carpet pad (8 lb.)
- Choice of Tile Floors in Master Bathroom & All Full Bathrooms
- Choice of LVT in all other rooms
- Stained Stair Treads, Risers & Stringers on Main Stairs

### **Value Added Amenities**

- New home orientation before move in
- New home backed by HBA Warranty
- Move-in follow up at 3 & 11 months
- Professionally cleaned interior of home